


# BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

## Schedule-B

**NAME OF WORK:** Repairs and extension of UGD lines in Abbigere village and surrounding area in ward No 12, Shettyhalli sub Division

| Sl. No | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | Unit | Qty     | Sanctioned rates |                |
|--------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|---------|------------------|----------------|
|        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |      |         | In Figures (Rs.) | In Words (Rs.) |
| 1      | 2                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | 3    | 4       | 5                | 6              |
| 1      | Earthwork excavation by manual means in hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications and as per the direction of Engineer-in-charge of the work.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | Cum  | 6089.75 | 189.74           |                |
| 2      | Providing and laying in position to required level or slope 230mm internal diameter salt glazed stoneware pipes grade A and jointing with stiff mixture of cement mortar in proportion of 1:1, testing of pipes and joints, including cost of materials, labour charges complete as per specifications and as per the direction of Engineer-in-charge of the work.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | Mtr  | 3206.40 | 568.16           |                |
| 3      | Providing and laying in position plain cement concrete M7.5 40mm and down size graded granite metal, machine mixed concrete laid in layers not exceeding 15 cms thick, well compacted, for 230mm internal diameter stoneware pipes including cost of materials, labour charges, HOM of machinery, curing complete as per specifications and as per the direction of Engineer-in-charge of the work.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | Mtr  | 530.00  | 518.34           |                |
| 4      | Constructing brick masonry circular type manhole 0.91m internal dia at bottom, 1.67m deep and 0.56m dia at top with table moulded non-modular bricks of 50 class designation 50 in cement mortar 1:4, inside cement plastered 12mm thick with cement mortar 1:3, finished with a floating coat of neat cement, foundation concrete M 10 using 40mm and downsize granite metal and making necessary channel in cement concrete M 50 with 20mm and downsize granite metal finished with a floating coat of neat cement, with S.F.R.C. cover and frame ( heavy duty, HD-20 grade designation) 560mm internal diameter confirming IS :12592, total weight cover and frame to be not less than 182 kg, fixed in cement concrete 1:2:4, 20mm and downsize broken granite metal, providing and removing centering, shuttering including cost of materials, labour charges, HOM of mechanies complete as per specifications. (Excavation, footrests and 12mm thick cement plaster on the external surface shall be paid seperately ) complete as per specifications and as per the direction of Engineer-in-charge of the work. | Nos  | 10.00   | 25741.04         |                |

  
EXECUTIVE ENGINEER-4  
KRIDL, BBMP DIVISON  
BENGALURU-560 010

  
EXECUTIVE ENGINEER  
Bruhat Bengaluru Mahanagara Palike  
Dasarahalli Division, Bengaluru-73.

ಎಸ್.ಎಂ. ರಸ್ತೆ, ದವೇಂದ್ರನಗರ, ಬಂಗಲೂರು

|   |                                                                                                                                                                                                                                                                                                                        |     |         |        |  |
|---|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----|---------|--------|--|
| 5 | Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m. and lift upto 1.5 m. including cost of all labour complete as per specifications and as per the direction of Engineer-in-charge of the work. | Cum | 6089.75 | 128.26 |  |
|---|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----|---------|--------|--|

Signature of Contractor

**EXECUTIVE ENGINEER-4**  
KRIDL, BBMP DIVISION  
BENGALURU-560 010

**EXECUTIVE ENGINEER**  
Bruhat Bengaluru Mahanagara Palike  
Dasarahalli Division, Bengaluru-73.